

Standard Operating Procedure QC-114: Incoming Material Inspection

Purpose: This SOP defines the inspection process for raw material received from approved suppliers. All incoming lots must be sampled according to ANSI/ASQ Z1.4 general inspection level II before being released to production. Rejected lots must be quarantined in the red-tag area within 2 hours of failed inspection.

SOP QC-114: Sampling and Acceptance Criteria

Sample size is determined by lot size per the AQL table, using an acceptable quality level of 1.0 for critical dimensions and 2.5 for cosmetic defects.

If the number of defective units in the sample exceeds the acceptance number, the entire lot is rejected. All measurements must be recorded on Form QC-114A and retained for 3 years for audit traceability.

SOP QC-114: Non-Conformance Handling

Any non-conforming material identified during inspection must be logged in the Non-Conformance Report (NCR) system within the same shift. The quality engineer on duty determines disposition: use-as-is, rework, return-to-vendor, or scrap. Disposition decisions require sign-off from both the quality manager and the production supervisor before material can be moved.